1. Carpet Inspection:

Check your carpet. Compare the carpet to your sample to make sure pattern, texture and color are the same. Check to make sure there are no visible defects before installation.

- 2. Seaming Layout: Review carpet seaming diagram. Seams should be placed in less visible areas.
- 3. Seam Sealing:

All carpet edges must be sealed with a seam or edge sealer to prevent raveling. Carpet must be cut with sharp cutting equipment / tools in order to prepare a smooth edge for seam sealing.

4. Carpet Pad:

Pad is necessary in for maximum carpet performance. J Mish recommends their all wool pad at 24 or 36 ounces or a quality fiber or urethane pad. Do not use wool pad in areas where moisture is an issue.

If there are any problems with your carpet that will prevent a quality installation, stop the installation and call J Mish Mills' Customer Service Department 800 655 8613.

Note: All warranties require proper installation and carpet maintenance. Claims for carpet cut and/or installed with obvious defects will not be honored.

For detailed installation steps refer to the Carpet and Rug Institute or Natural Fiber Institute guidelines: CRI 105 - Standard for Installation of Residential Carpet CRI 104 - Standard for Installation of Commercial Carpet <u>http://www.carpet-rug.org/Industry-Resources/CRI-Installation-Standard.aspx</u>

Natural Fiber Institute – Installation Guidelines for Tufted Wool Carpet http://nficnet.com/installation-guidelines/tufted-wools/